



Pole Line Infrastructure Removals - Ocean Westway and Crowley Road

APPENDIX "B"

SCOPE DETAILS

1. SCOPE

1.1. POLE LINE INFRASTRUCTURE REMOVALS

Saint John Energy (SJE) routinely requires the removal of discontinued pole line infrastructure within the City of Saint John. Examples would be the removal of an end of life back lot pole line when the new pole line has been commissioned in the roadway right of way.

Ocean Westway

The discontinued pole line is 15 span in length and back lot construction with alders. The removal will consist of 650m 3 phase primary conductor, 340m neutral conductor and 325 span secondary conductor, 11 poles and 7 anchors. Pole holes must be filled in and all debris removed from site including cut alders. Vehicles must stay within 3m of either side of the actual pole line due to customer infrastructure (preferably on the highway side of the pole line).

Scrap metal components and wire will be returned to SJE for recycling and wood material disposal will be the contractor's responsibility.

See Attachment 1 Ocean Westway Pole Line Removal Detail Package.

Work site visit mandatory.

Crowley Road

The discontinued pole line is 13 span in length and back lot construction. The removal will consist of 320m single phase primary conductor, 320m neutral conductor, 398m secondary conductor, 2 services, 12 poles and 1 anchor. Pole holes must be filled in and all debris removed from site including cut tree limbs. Vehicles must stay within 3m feet of either side of the actual pole line due to customer infrastructure. (Preferably on the field side of the pole line).

Scrap metal components and wire will be returned to SJE for recycling and wood material disposal will be the contractor's responsibility.

See Attachment 2 Crowley Road Pole Line Removal Detail Package.

Work site visit mandatory.

Saint John Energy requires that all disturbed grounds to be restored back to original or better condition.

2. CONTRACTOR'S RESPONSIBILITIES

The Contractor shall provide all labor, equipment and material (unless stated in Section 3.1 – Items Provided by Company) to complete the removal of the pole line infrastructure listed in Section 3.1 and in the attached drawings. This work may be completed during Saint John Energy's normal operating hours or after hours.

The Contractor shall wear all proper Personal Protective Equipment (PPE) while working for the Company.

The Proponents may be asked to submit a work plan/schedule example detailing out how they propose to complete the works within a given time line.

2.1 WORKING AROUND ENERGIZED EQUIPMENT

The Contractor may be required to complete the work in the proximity to energized equipment, and must follow Saint John Energy's Standard Work method SWM 8.04.04. This will require a minimum of 1 contractor Power Line Technician on site during the work.

2.2 TRAFFIC CONTROL

The Contractor shall complete all work under this contract in a safe manner for traveling public and for all personnel on the work site. Traffic control shall be the responsibility of the Contractor and shall be carried out in accordance with the City of Saint John's traffic control policies. The Authorized Representative may require the submission of Traffic Control Plan(s) which clearly illustrate the layout and procedures to be followed. When Traffic Control Plans are required, they must be accepted by the Authorized Representative prior to commencement of any work. Traffic Control Signs, as required, shall be supplied, installed and maintained by the Contractor.

2.3 SAFETY

Due to the hazardous working area, the contractor shall complete a daily documented safety meeting to go over the day's activities and associated hazards. The Saint John Energy Site Supervisor shall be part of this meeting when required. Daily safety documents shall be available upon request and any new persons on site will be required to review and sign off before entering the site, this includes the Contractor's employees, subcontractors, and Saint John Energy employees.

A template for daily safety meeting documents can be supplied by Saint John Energy upon request.

2.4 CONTRACTOR'S EQUIPMENT

The Contractor shall provide and maintain in good working order, adequate equipment to perform the Work in accordance with the approved schedule. All such equipment shall be subject to the approval of the Company.

2.5 CONTRACTOR IDENTIFICATION

All Contractor and sub-contracted vehicles working on this project must be properly identified with their company's logo(s).

2.6 CODE OF CONDUCT FOR CONTRACTORS

All Contractors, their employees including Subcontractors are responsible for conducting themselves in a professional, ethical and legal manner while performing Work for the Company.

3. COMPANY'S RESPONSIBILITIES

The Company shall supply all materials listed in 3.1 - Items provided by the Company to the Contractor. All other parts deemed necessary for the Work will be supplied by the Contractor. The Company may deliver the material to site on an agreed upon date with the contractor; otherwise, the contractor is responsible to deliver material to the site. After delivered at site, the contractor will take full responsibility for the material and its security.

3.1 ITEMS SUPPLIED BY THE COMPANY

The Company will provide the following to the Contractor when and where applicable;

- Scrap aluminum wire storage lockers at 325 Simms Street
- Scrap copper wire storage lockers at 325 Simms Street
- Scrap mixed metal bin at 325 Simms Street

All items provided to the Contractor shall remain the property of the Company.

The Contractor shall be responsible for the proper use and security of all items provided by the Company. The Contractor shall immediately notify the Company when any items are lost, stolen or damaged while under the Contractor's care. The lost, stolen or damaged items shall be replaced by the Company and the cost of the replacements charged to the Contractor.

4 INSPECTION BY THE COMPANY

The Company shall have the right to inspect the Work at all times, and will be doing so on a regular basis and the Company may reject any part of the Work thereof which is not in accordance with the Contract. Any of the Work so rejected, shall forthwith be re-executed or corrected by the Contractor, as its sole expense and in a manner prescribed by the Contract, but if in the opinion of the Company it is not feasible to re-execute or correct the rejected Work, the Company shall be bound to pay to the Contractor only such sums of money as, in the opinion of the Company, represents the value of the Work to the Company.

5 HOURS OF WORK

It is anticipated that the works will be carried out during Saint John Energy's normal hours of work between 8:00 a.m. and 5:00 pm, however the contractor may work any other desired hours if they do not violate any of the City of Saint John's bylaws.

6 SUBCONTRACTORS

The Contractor shall be responsible for engaging Subcontractors as required, to ensure that the installation schedule requirements are met.

The Proponent shall include a list of Subcontractors as a part of their offering.

If the Contractor engages a new subcontractor during the schedule of the works, the Company shall be notified in writing in advance of a Subcontractor commencing any of the works related to this scope.

The Company reserves the right to approve all proposed Subcontractors and employees.

7 TRAINING

All Contractors, as well as subcontractors, must ensure that their employees are trained to perform their Work in a manner that will ensure their safety, the safety of Saint John Energy employees and the general public. All Contractors must be qualified and competent to perform their assigned task as per Occupational Health & Safety Regulations and in accordance with the requirements of this Contract.

The Company will provide training/instruction (at no cost to the Company or the Contractor) as may be required from time-to-time to accommodate upgrades or changes to the Company's requirements.

8 ABNORMAL CONDITIONS

The Contractor must report any abnormal conditions that may arise to the Company's Authorized Representative in a timely manner.

9 NEWS RELEASES

Information for publicity of any nature with respect to any facet on the Company's business or operations or of the Work being performed on Site by the Contractor or others, shall not be released or disclosed without prior consent of the Company's Authorized Representative.

10 CHANGE IN THE WORK

The Company may, without invalidating the contract, direct the Contractor to make changes in the Work.

When a change causes an increase or decrease in the Work, the contract price shall be increased or decreased by the application of unit prices to the quantum of such increase or decrease or, in the absence of applicable unit prices, by an amount to be agreed upon between the Contractor and the Company prior to the commencement of any additional works.

The Contractor may not increase costs without consent of the Company.